

## **Annexure I for Group-A**

### **(For CHAMBER of Size 1.2 m X1.2m)**

**Item no.1:** Earthwork in excavation for foundation trenches of walls , retaining walls, footing of columns, steps ,septic tanks etc. including refilling the quantity as necessary after completion of work, breaking clods in return filling including dressing, watering and ramming etc. and removal of surplus earth with all lead and lifts as directed and specified bailing out water where necessary as directed and specified . (A) Up to a depth of 2m below the existing ground level (d) In medium rock of hard shale

**Item no.2:** Providing soling in foundation and under floor at all levels with stone/best quality picked Jhama bricks , sand packed and laid to level and in panel after preparing the sub-grade as directed including all labour and materials complete a) Brick flat soling

**Item no.3:** Plain cement concrete works with coarse aggregate of sizes 13mm to 32mm in foundation bed for footing , steps ,walls ,brick works etc. as directed and specified including curing complete. b) In prop. 1:3:6

**Item no.4 :** Supplying ,fitting and fixing in position reinforcement bars for R.C.C. work including straightening , cleaning , cutting and bending to proper shapes and length as per details , supplying and binding with 20G annealed black wire and placing in position with proper blocks , supports , chairs , spacers etc. complete

(ii)Super Ductile (SD) TMT reinforcement bars

**Item no.5 :** Providing formworks of ordinary timber planking so as to give a rough finish including centering, shuttering , strutting and propping etc.. Height of propping and centering below supporting floor to ceiling and removal of the same of in situ reinforced concrete and plain concrete work

(ii) Using 25mm thick plank

**Item no.6 :** Providing and laying plain/reinforced cement concrete works in prop.1:1.5:3 including curing complete but excluding cost of formwork and reinforcement for reinforced cement concrete work .

a) In sub structure up to plinth level . Foundation, footing , columns with base, tie and plinth beam, pile cap, base slab , retaining walls, walls of septic tank , inspection pit and the like and other works not less than 10 cm thick up to plinth level.

**Item no.7 :** Brick work in cement mortar with 1st class brick including racking out joints and curing complete as directed.

(b) In cement mortar in proportion 1:4. (1 cement:4 sand)

**Item no.8 :** 12 mm thick Cement Plastering including clearing the surface and curing etc completed b) In prop. 1:4





**Annexure-II for Group-A**  
**(For 1 Panel Board Shed)**

Item of Work :

1	Brick soling under foundation and floor with 1st. Class bricks as directed. (i) Flate soling.
2	65mm thick c.c Flooring 1:2:4 finished with a floating coat of neat cement finish to be laid in panels including curing complete as directed.
3	15mm thick cement plaster in single coat on wrough side of single or half brick wall i/c curing complete as directed.(i) In propn 1 : 4.
4	Cement plaster skirting with cement mortar in propn. 1 : 3 finished with a floating coat of neat cement i/c rounding of junctions with floor.(i) 15mm thick.
5	Providing undressed wood work in roof truss , rafter, purlin i/c supplying and fitting with necessary spikes and nails etc. complete as directed. (b) With Hollock /Sundi / Sam
6	Providing Pre Painted Galvanized Iron Sheet Roofing (PPGI) at all levels including fitting and fixing with self drilling, self tapping screws complete. (Roof trusses, purlins etc. to be measured and paid separately.) TATA Blue scope/ Dyna roof / Durakolor /Wonder Roof or equivalent as directed by the Departement (iii) 0.50 mm thick
7	Providing and fixing flush door shutters solid core construction with frame of .... c) One face decorative and other face nondecorative type and block board core. (iii) 30mm thk.
8	Providing, fitting and fixing M.S. grill of required pattern..... squire or round M.S. bars with round headed bolts and nuts or screws. II Ornamental grill (c) Fixed to Brickwork/P.C.C/R.C.C.
9	g) Distempering with dry distemper of approved brand and manufacture (twocoats) and of required shade on new wall surface.... and including preparing surface even and sand papered smooth.



